



**TOWN OF WESTWOOD
COMMONWEALTH OF MASSACHUSETTS**

INVITATION FOR BIDS

Far Reach Road Pump Station Upgrades

Bid # DPW-21-B-004

Addendum 02

June 5, 2020

I. GENERAL INFORMATION

Addendum 02 answers the following questions:

- Q4 Could you please clarify what is being painted / coated at Far Reach Road?
A4 The painting work associated with Bid Item 4 – Painting is limited to painting portions of the pump room walls that are stained from groundwater infiltration and areas that are impacted by the injection grouting process.
- Q5 The Bilco Hatch is an H-20. This hatch is “structural” Which means you can NOT install Safety Grating, only Safety Netting.
A5 See the following response from Bilco below:
“Our grating is a hinged cover that goes below the solid steel cover of the h20 door. We feel this hinged grate is less cumbersome to operate than a safety net.”
- Q6 The time and material for concrete rehab around the hatch is very time consuming. Would the Owner entertain a new hatch with Grating or mesh and new structure cover?
A6 For bidding purposes, the wet well top slab rehabilitation shall be completed as shown and described in the Contract Documents.
- Q7 The Hot top around this structure should be replaced so the correct grading is achieved. It is a much larger area than I think was initially anticipated. After reviewing the site the conclusion that we came to was the following: Hot top area is sunken, making plows etc hit the top of the structure and water to puddle. This will negatively affect the integrity of the concrete, especially with Ice Melt products. We feel a larger area of hot top than initially thought be replaced. Having the correct subgrade elevation will achieve the correct hot top/final elevation desired to no longer make this an issue.
A7 Bid Item 3 – Wet Well Rehabilitation and Fall Protection shall include restoring all disturbed area associated with the rehabilitation work covered under the bid item. All disturbed areas shall be restored to preconstruction conditions. **Add the following text to Section 01024-2, Item 1.2, Paragraph C:**
“3. The Contractor shall perform all work required to completely restore all disturbed areas to pre-construction conditions”
- Q8 What is the average daily flow through the station?
A8 The average daily flow is 13,500 GPD.
- Q9 How long is the force main?
A9 The force main length is approximately 500 feet.



**TOWN OF WESTWOOD
COMMONWEALTH OF MASSACHUSETTS**

II. ADDENDUM 02 RECEIPT ACKNOWLEDGEMENT FORM

BIDDERS MUST ACKNOWLEDGE RECEIPT OF ADDENDUM WITH THE BID SUBMITTAL.

Signature _____

Name _____

(Please Print)

Title _____

Company _____

Date _____

End of Addendum No. 2