

MISCELLANEOUS PAVING - PAVEMENT MANAGEMENT PROGRAM - 2021

TOWN OF WESTWOOD, MA


MARCH 2021

INDEX

01	TITLE SHEET & INDEX
02	LEGEND AND ABBREVIATIONS
03	GENERAL NOTES
04	LOCUS MAP
05	TYPICAL SECTIONS
06	CONSTRUCTION DETAILS
07	POND STREET & CLAPBOARDTREE STREET CONSTRUCTION PLANS & PAVEMENT MARKING PLANS

PUBLIC WORKS DEPARTMENT
50 CARBY STREET
WESTWOOD, MA 02090

TODD KORCHIN, DIRECTOR OF PUBLIC WORKS



GENERAL SYMBOLS

EXISTING	PROPOSED	DESCRIPTION
		JERSEY BARRIER
		CATCH BASIN
		CATCH BASIN CURB INLET
		FLAG POLE
		GAS PUMP
		MAIL BOX
		ELECTRIC HANDHOLE
		FENCE GATE POST
		GAS GATE
		BORING HOLE
		HYDRANT
		LIGHT POLE
		COUNTY BOUND
		GPS POINT
		CABLE MANHOLE
		DRAINAGE MANHOLE
		ELECTRIC MANHOLE
		GAS MANHOLE
		MISC MANHOLE
		SEWER MANHOLE
		TELEPHONE MANHOLE
		WATER MANHOLE
		MASSACHUSETTS HIGHWAY BOUND
		MONUMENT
		STONE BOUND
		TOWN OR CITY BOUND
		TRAVERSE OR TRIANGULATION STATION
		UTILITY POLE W/ FIREBOX
		UTILITY POLE WITH DOUBLE LIGHT
		UTILITY POLE W / 1 LIGHT
		UTILITY POLE
		BUSH
		TREE
		STUMP
		SWAMP / MARSH
		WATER GATE
		PARKING METER
		OVERHEAD CABLE/WIRE
		CURBING
		CONTOURS (ON-THE-GROUND SURVEY DATA)
		CONTOURS (PHOTOGRAMMETRIC DATA)
		UNDERGROUND DRAIN PIPE (DOUBLE LINE 24 INCH AND OVER)
		UNDERGROUND ELECTRIC DUCT (DOUBLE LINE 24 INCH AND OVER)
		UNDERGROUND GAS MAIN (DOUBLE LINE 24 INCH AND OVER)
		UNDERGROUND SEWER MAIN (DOUBLE LINE 24 INCH AND OVER)
		UNDERGROUND TELEPHONE DUCT (DOUBLE LINE 24 INCH AND OVER)
		UNDERGROUND WATER MAIN (DOUBLE LINE 24 INCH AND OVER)
		BALANCED STONE WALL
		CHAIN LINK OR METAL FENCE
		WOOD FENCE
		HAY BALES/SILT FENCE
		TREE LINE
		SAWCUT LINE
		TOP OR BOTTOM OF SLOPE
		LIMIT OF EDGE OF PAVEMENT OR COLD PLANE AND OVERLAY
		BANK OF RIVER OR STREAM
		BORDER OF WETLAND
		100 FT WETLAND BUFFER
		200 FT RIVERFRONT BUFFER
		STATE HIGHWAY LAYOUT
		TOWN OR CITY LAYOUT
		COUNTY LAYOUT
		RAILROAD SIDELINE
		TOWN OR CITY BOUNDARY LINE
		PROPERTY LINE OR APPROXIMATE PROPERTY LINE
		EASEMENT

PAVEMENT MARKINGS SYMBOLS

EXISTING	PROPOSED	DESCRIPTION
		PAVEMENT ARROW - WHITE
		LEGEND "ONLY" - WHITE
		STOP LINE - 12" WIDE
		CROSSWALK
		SOLID WHITE LINE - 6" WIDE
		SOLID YELLOW LINE - 6" WIDE
		BROKEN WHITE LINE - 10' LINE W/ 30' SPACING - 6" WIDE
		BROKEN YELLOW LINE - 10' LINE W/ 30' SPACING - 6" WIDE
		DOTTED WHITE LINE - 3' LINE W/ 9' SPACING - 6" WIDE
		DOTTED YELLOW LINE - 3' LINE W/ 9' SPACING - 6" WIDE
		DOTTED WHITE LINE EXTENSION - 2' LINE W/ 6' SPACING - 6" WIDE
		DOTTED YELLOW LINE EXTENSION - 2' LINE W/ 6' SPACING - 6" WIDE
		DOUBLE YELLOW LINE - 6" WIDE
		SOLID WHITE CHANNELIZATION LINE - 12" WIDE
		SOLID YELLOW CHANNELIZATION LINE - 12" WIDE

ABBREVIATIONS - GENERAL

AADT	ANNUAL AVERAGE DAILY TRAFFIC
ABAN	ABANDON
ADJ	ADJUST
APPROX.	APPROXIMATE
BIT.	BITUMINOUS
BC	BOTTOM OF CURB
BD.	BOUND
BL	BASELINE
BLDG	BUILDING
BM	BENCHMARK
BO	BY OTHERS
BOS	BOTTOM OF SLOPE
BS	BARE STEEL
CB	CATCH BASIN
CBCI	CATCH BASIN WITH CURB INLET
CEM	CEMENT
CI	CURB INLET
CIP	CAST IRON PIPE
C.I.T.	CHANGE IN TYPE
CLF	CHAIN LINK FENCE
CL	CENTERLINE
CMP	CORRUGATED METAL PIPE
CRW	CONCRETE RETAINING WALL
CSP	CORRUGATED STEEL PIPE
CO.	COUNTY
CONC	CONCRETE
CONT	CONTINUOUS
CONST	CONSTRUCTION
CR GR	CROWN GRADE
DI	DROP INLET
DIA	DIAMETER
DIP	DUCTILE IRON PIPE
DSMH	DEEP SUMP MANHOLE
DW	STEADY DON'T WALK
DWY	DRIVEWAY
ELEV (or EL.)	ELEVATION
EOP	EDGE OF PAVEMENT
EXIST (or EX)	EXISTING
F&C	FRAME AND COVER
F&G	FRAME AND GRATE
FLDSTN	FIELDSTONE
GAR	GARAGE
GD	GROUND
GG	GAS GATE
GI	GUTTER INLET
HMA	HOT MIX ASPHALT
HOR	HORIZONTAL
HYD	HYDRANT
INV	INVERT
IP	INTERMEDIATE PRESSURE
L	LENGTH OF CURVE
LP	LIGHT POLE
LP	LOW PRESSURE
LT	LEFT
MAX	MAXIMUM
MB	MAILBOX
MH	MANHOLE
MHB	MASSACHUSETTS HIGHWAY BOUND
MIN	MINIMUM
NIC	NOT IN CONTRACT
NO.	NUMBER
PBS	PRINT BOTH SIDES
PC	POINT OF CURVATURE
PCC	POINT OF COMPOUND CURVATURE
PD	ALDYL "A" PLASTIC
P.G.L.	PROFILE GRADE LINE
PI	POINT OF INTERSECTION
PKF	PICKET FENCE
POT	POINT ON TANGENT
PRC	POINT OF REVERSE CURVATURE
PRF	POST AND RAIL FENCE
PROJ	PROJECT
PROP	PROPOSED

ABBREVIATIONS - GENERAL

PT	POINT OF TANGENCY
PVC	POINT OF VERTICAL CURVATURE
PVI	POINT OF VERTICAL INTERSECTION
PVT	POINT OF VERTICAL TANGENCY
PVMT	PAVEMENT
PWW	PAVED WATER WAY
PY	YELLOW PLASTIC
R	RADIUS OF CURVATURE
R&D	REMOVE AND DISPOSE
RCP	REINFORCED CONCRETE PIPE
REM	REMOVE
RET	RETAIN
RET WALL	RETAINING WALL
ROW	RIGHT OF WAY
R&R	REMOVE AND RESET
R&S	REMOVE AND STACK
RT	RIGHT
SB	STONE BOUND
SHLDR	SHOULDER
SMH	SEWER MANHOLE
ST	STEEL
ST	STREET
STA	STATION
SSD	STOPPING SIGHT DISTANCE
SHLO	STATE HIGHWAY LAYOUT LINE
SMRW	STONE MASONRY RETAINING WALL
SRW	STONE RETAINING WALL
SW	SIDEWALK
T	TANGENT DISTANCE OF CURVE/TRUCK %
TAN	TANGENT
TEMP	TEMPORARY
TC	TOP OF CURB
TOS	TOP OF SLOPE
TYP	TYPICAL
UGE	UNDERGROUND ELECTRIC
UP	UTILITY POLE
VAR	VARIES
VERT	VERTICAL
VC	VERTICAL CURVE
VCC	VERTICAL CONCRETE CURB
VGC	VERTICAL GRANITE CURB
WCR	WHEEL CHAIR RAMP
WG	WATER GATE
WI	WROUGHT IRON
WIF	WROUGHT IRON FENCE
WIP	WROUGHT IRON PIPE
WM	WATER METER/WATER MAIN



Scale	AS NOTED	
Date	MARCH 2021	
Job No.	R309-2009	
Designed by	AMF	
Drawn by	AMF	
Checked by	MES	
Approved by	JDF	
MARK	DATE	DESCRIPTION

THIS LINE IS ONE INCH LONG WHEN PLOTTED AT FULL SCALE ON A 22" X 34" DRAWING

MISCELLANEOUS PAVING - PAVEMENT MANAGEMENT PROGRAM - 2021 WESTWOOD, MA

LEGEND & ABBREVIATIONS

Sheet No.

02

GENERAL CONSTRUCTION NOTES:

- CONSTRUCTION SHALL BE IN CONFORMANCE WITH THE FOLLOWING: THE MASSACHUSETTS HIGHWAY DEPARTMENT STANDARD SPECIFICATIONS FOR HIGHWAYS AND BRIDGES DATED 2021, AS AMENDED, THE 2017 CONSTRUCTION STANDARD DETAILS, THE 1996 CONSTRUCTION AND TRAFFIC STANDARD DETAILS (AS RELATES TO TRAFFIC STANDARD DETAILS ONLY), THE LATEST MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES FOR STREETS AND HIGHWAYS WITH LATEST REVISIONS AND MASSACHUSETTS AMENDMENTS, THE 1990 STANDARD DRAWINGS FOR SIGNS AND SUPPORTS, THE 1968 STANDARD DRAWINGS FOR TRAFFIC SIGNALS AND HIGHWAY LIGHTING AND THE LATEST EDITION OF THE AMERICAN STANDARD FOR NURSERY STOCK.
- THE TERM "PROPOSED" (PROP) MEANS WORK TO BE CONSTRUCTED HEREIN USING NEW MATERIALS OR WHERE APPLICABLE, REUSING EXISTING MATERIALS IDENTIFIED AS "REMOVE AND RESE" (R&R). ALL OTHER MATERIALS SHALL BE "REMOVED AND DISCARDED" (R&D) OR DISPOSED OF OFF SITE WITH THE EXCEPTION OF MATERIALS LABELED AS "REMOVED AND STACKED" (R&S) WHICH SHALL BE TRANSPORTED AND AND STACKED AT A LOCATION DESIGNATED BY THE TOWN AND OR ENGINEER.
- MAKE ALL NECESSARY CONSTRUCTION NOTIFICATIONS AND APPLY FOR AND OBTAIN ALL NECESSARY CONSTRUCTION PERMITS, PAY ALL FEES INCLUDING POLICE DETAILS AND POST ALL BONDS, IF NECESSARY, ASSOCIATED WITH THE SAME, AND COORDINATE WITH THE OWNER AND THE ENGINEER.
- THE CONTRACTOR SHALL NOT STORE ANY APPARATUS, MATERIALS, SUPPLIES, OR EQUIPMENT ON DRAINAGE STRUCTURES, PRIVATE PROPERTY OR WITHIN 100 FEET OF WETLANDS, UNLESS DIRECTED TO DO SO BY THE CONTRACT DOCUMENTS.
- ALL EXISTING CONDITIONS SHOWN ARE APPROXIMATE AND ARE BASED ON THE BEST INFORMATION AVAILABLE. PRIOR TO THE START CONSTRUCTION VERIFY THAT THE PROPOSED IMPROVEMENTS SHOWN ON THE PLANS DO NOT CONFLICT WITH ANY KNOWN EXISTING OR OTHER PROPOSED IMPROVEMENTS. IF ANY CONFLICTS ARE DISCOVERED, NOTIFY THE OWNER AND THE ENGINEER PRIOR TO INSTALLING ANY PORTION OF THE SITE WORK WHICH WOULD BE AFFECTED.
- THE LOCATION AND/OR ELEVATION OF EXISTING UTILITIES AND STRUCTURES AS INDICATED ON THE DRAWINGS ARE BASED ON RECORDS OF VARIOUS UTILITY COMPANIES, AND WHEREVER POSSIBLE, MEASUREMENTS TAKEN IN THE FIELD. THIS INFORMATION IS NOT TO BE RELIED UPON AS BEING EXACT OR COMPLETE. VERIFY THE LOCATION OF ALL UNDERGROUND UTILITIES AND STRUCTURES IN THE FIELD PRIOR TO THE START OF CONSTRUCTION. CONTACT THE APPROPRIATE UTILITY COMPANY, ANY GOVERNING PERMITTING AUTHORITY IN THE TOWN, AND "DIGSAFE" (1-888-344-7233) AT LEAST 72 HOURS PRIOR TO ANY EXCAVATION WORK IN PREVIOUSLY UNALTERED AREAS TO REQUEST EXACT FIELD LOCATION OF UTILITIES. THE CONTRACTOR MUST RESOLVE CONFLICTS BETWEEN THE PROPOSED UTILITIES AND FIELD-LOCATED UTILITIES AND REPORT ANY DISCREPANCIES TO THE ENGINEER IMMEDIATELY. THE ENGINEER ASSUMES NO RESPONSIBILITY FOR DAMAGES INCURRED AS A RESULT OF UTILITIES OMITTED, INCOMPLETELY OR INACCURATELY SHOWN. THE CONTRACTOR MUST MAINTAIN ACCURATE RECORDS OF THE LOCATION AND ELEVATION OF ALL WORK INSTALLED AND EXISTING UTILITIES FOUND DURING CONSTRUCTION FOR THE PREPARATION OF THE AS-BUILT PLAN.
- THE CONTRACTOR SHALL COORDINATE ALL ARRANGEMENTS FOR THE ALTERATION AND OR ADJUSTMENT OF ELECTRIC, TELEPHONE, GAS AND ANY OTHER PRIVATE UTILITY.
- SHOULD AN EXISTING UTILITY BE FOUND TO BE IN CONFLICT WITH THE PROPOSED WORK, THE LOCATION, SIZE AND TYPE SHALL BE ACCURATELY DETERMINED WITHOUT DELAY, BY THE CONTRACTOR, AND THE INFORMATION FURNISHED TO THE TOWN AND OR ENGINEER FOR RESOLUTION OF THE CONFLICT.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR ADJUSTING OR REMODELING ALL DRAINAGE, WATER, OR SEWER STRUCTURES TO THE FINISHED ELEVATION, WITHIN THE LIMITS OF THE PROJECT, UNLESS OTHERWISE NOTED.
- THE CONTRACTOR SHALL PERFORM TEST PITS AT LOCATIONS SHOWN ON PLAN AND AS DIRECTED BY THE TOWN AND OR ENGINEER.
- ALL WORK TO COMPLETE THIS PROJECT AS INDICATED ON THE DRAWINGS AND IN THE SPECIFICATIONS IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR.
- THE CONTRACTOR MUST MAINTAIN ALL EXISTING UTILITIES IN WORKING ORDER AND FREE FROM DAMAGE DURING THE ENTIRE DURATION OF THE PROJECT. REPAIR ANY DAMAGE TO EXISTING UTILITY LINES OR STRUCTURES INCURRED DURING CONSTRUCTION OPERATIONS AT NO COST TO THE OWNER. THE CONTRACTOR IS RESPONSIBLE FOR ALL COST RELATED TO THE REPAIR OF UTILITIES. EXCAVATION REQUIRED WITHIN THE PROXIMITY OF EXISTING UTILITY LINES MUST BE DONE BY HAND
- COORDINATE ALL TRENCHING WORK WITHIN ROADWAYS WITH THE PROPER LOCAL & STATE AGENCY. THE CONTRACTOR IS RESPONSIBLE FOR ALL TRENCH SAFETY INCLUDING ANY LOCAL AND/OR STATE PERMITS REQUIRED FOR THE TRENCH WORK. IF THIS WORK IS REQUIRED TO OCCUR OUTSIDE THE AGREED UPON HOURS OF OPERATION FOR THE FACILITY, THE CONTRACTOR MUST PLAN ACCORDINGLY.
- INSTALL ALL UTILITY TRENCH WORK PRIOR TO INSTALLING NEW PAVEMENT AS INDICATED ON THE DRAWINGS.
- IMPORT ONLY CLEAN MATERIAL. MATERIAL FROM AN EXISTING OR FORMER 21E SITE AS DEFINED BY THE MASSACHUSETTS CONTINGENCY PLAN 310 CMR 40.0000 WILL NOT BE ACCEPTED .
- IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO ESTABLISH AND MAINTAIN ALL CONTROL POINTS AND BENCHMARKS DURING CONSTRUCTION INCLUDING BENCHMARK LOCATIONS AND ELEVATIONS AT CRITICAL AREAS. COORDINATE WITH THE ENGINEER THE LOCATION OF ALL CONTROL POINTS AND BENCHMARKS.
- SITE LAYOUT SURVEY REQUIRED FOR CONSTRUCTION MUST BE PROVIDED BY THE CONTRACTOR AND PERFORMED BY A MASSACHUSETTS' REGISTERED PROFESSIONAL LAND SURVEYOR. THE CONTRACTOR IS RESPONSIBLE FOR COORDINATING WITH THE SURVEYOR FOR ALL SITE SURVEY WORK.
- MAINTAIN ALL GRADE STAKES SET BY THE SURVEYOR. GRADE STAKES ARE TO REMAIN UNTIL A FINAL INSPECTION OF THE ITEM HAS BEEN COMPLETED BY THE ENGINEER. RE-STAKING OF PREVIOUSLY SURVEYED SITE FEATURES IS THE RESPONSIBILITY (INCLUDING COST) OF THE CONTRACTOR.
- PROVIDE ALL CONSTRUCTION SERVICE IN ACCORDANCE WITH APPLICABLE LAWS AND REGULATIONS REGARDING NOISE, VIBRATION, DUST, SEDIMENTATION CONTAINMENT, AND TRENCH WORK.
- COLLECT SOLID WASTES AND STORE IN A SECURED DUMPSTER. THE DUMPSTER MUST MEET ALL LOCAL AND STATE SOLID WASTE MANAGEMENT REGULATIONS.

GENERAL NOTES CONTINUED:

- REGULARLY INSPECT THE PERIMETER OF THE PROPERTY TO CLEAN UP AND REMOVE LOOSE CONSTRUCTION DEBRIS BEFORE IT LEAVES THE SITE. PROMPTLY REMOVE ALL DEMOLITION DEBRIS FROM THE SITE TO AN APPROVED DUMP SITE.
- ALL TRUCKS LEAVING THE SITE MUST BE COVERED.
- DO NOT WASH ANY CONCRETE TRUCKS ONSITE. REMOVE BY HAND ANY CEMENT OR CONCRETE DEBRIS LEFT IN THE DISTURBED AREA.
- BURIAL OF ANY STUMPS, SOLID DEBRIS, AND/OR STONES/BOULDERS ONSITE IS PROHIBITED.
- IMMEDIATELY CONTACT AND COORDINATE WITH THE ENGINEER AND OWNER IF ANY DEVIATION OR ALTERATION OF THE WORK PROPOSED ON THESE DRAWINGS IS REQUIRED.
- AT THE END OF CONSTRUCTION, REMOVE ALL CONSTRUCTION DEBRIS AND SURPLUS MATERIALS FROM THE SITE PERFORM A THOROUGH INSPECTION OF THE WORK PERIMETER. COLLECT AND REMOVE ALL MATERIALS AND BLOWN OR WATER CARRIED DEBRIS FROM THE SITE.
- THE CONTRACTOR SHALL PROVIDE FOR THE SAFE AND ORDERLY PASSAGE OF VEHICULAR AND PEDESTRIAN TRAFFIC IN AREAS UNDER CONSTRUCTION.
- SHOP DRAWINGS OF ALL CASTINGS, PRECAST CONCRETE STRUCTURES, PIPE AND MANUFACTURED COMPONENTS SHALL BE SUBMITTED FOR APPROVAL BEFORE ORDERING.
- ALL PROPOSED PAVEMENT MARKINGS SHALL MEET EXISTING MARKINGS AT THE LIMITS OF WORK.
- SEE SIGNS AND PAVEMENT MARKING PLANS FOR PROPOSED SIGNS AND DISPOSITION OF THE EXISTING SIGNS WITHIN THE PROJECT LIMITS OR AS DIRECTED BY THE TOWN.
- DO NOT SCALE DRAWINGS UNLESS OTHERWISE NOTED. WRITTEN DIMENSIONS SHALL PREVAIL. REPORT ANY DISCREPANCIES TO THE ENGINEER IMMEDIATELY.
- THE CONTRACTOR SHALL COMPLY WITH ALL APPLICABLE REGULATIONS OF THE OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION (OSHA).THE CONTRACTOR SHALL RESTORE ALL PUBLIC AND PRIVATE PROPERTY TO ITS PRE-CONSTRUCTION CONDITION AT NO ADDITIONAL COST TO THE TOWN.
- THE CONTRACTOR SHALL RESTORE ALL PUBLIC AND PRIVATE PROPERTY TO ITS PRE-CONSTRUCTION CONDITION AT NO ADDITIONAL COST TO THE TOWN.
- ALL EXISTING UTILITIES LINES ENCOUNTERED DURING CONSTRUCTION ARE TO REMAIN IN SERVICE. THE CONTRACTOR, AT NO ADDITIONAL COST TO THE TOWN, SHALL REPAIR ANY EXISTING SEWERS, GAS LINE, WATER MAINS, STORM DRAIN LINES, OR CULVERTS DAMAGED DURING CONSTRUCTION.
- IN THOSE INSTANCES WHERE POWER OR TELEPHONE POLE SUPPORT IS REQUIRED, THE CONTRACTOR SHALL PROVIDE A MINIMUM 48-HOUR NOTIFICATION TO THE RESPECTIVE UTILITY COMPANY. NO ADDITIONAL PAYMENT WILL BE PROVIDED FOR TEMPORARY BRACING OF UTILITIES.
- ALL STRUCTURES AND PIPELINES LOCATED ADJACENT TO THE TRENCH EXCAVATION SHALL BE PROTECTED AND FIRMLY SUPPORTED BY THE CONTRACTOR UNTIL THE TRENCH IS BACKFILLED. INJURY TO ANY SUCH STRUCTURE CAUSED BY, OR RESULTING FROM, THE CONTRACTOR'S OPERATIONS SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE. ALL UTILITIES REQUIRING REPAIR, RELOCATION OR ADJUSTMENT AS A RESULT OF THE PROJECT SHALL BE COORDINATED THROUGH THE RESPECTIVE UTILITY AND THE TOWN.
- THE CONTRACTOR IS TO TAKE SPECIAL CARE NOT TO DAMAGE TREES, BUSHES, PLANTS, FLOWERS, STONEWALLS, FENCES, ETC. WITHIN THE CONSTRUCTION AREA UNLESS THEY ARE NOTED TO BE REMOVED. CONTRACTOR SHALL REPLACE AT NO COST TO OWNER, ALL DAMAGED ITEMS.
- CONTRACTOR SHALL REMOVE AND REPLACE, OR REPAIR, ALL CURBS, SIDEWALKS, PAVEMENT AND OTHER ITEMS DAMAGED BY HIS CONSTRUCTION ACTIVITIES TO AT LEAST THEIR ORIGINAL CONDITION, AND TO THE SATISFACTION OF THE TOWN AND ENGINEER.
- ANY TRAFFIC SIGNAL EQUIPMENT (LIGHTS, CONDUITS, LOOP DETECTORS) DISTURBED SHALL BE REPAIRED OR REPLACED BY THE CONTRACTOR AS DIRECTED BY THE TOWN AT THE CONTRACTOR'S EXPENSE.
- THE CONTRACTOR SHALL INSTALL AND MAINTAIN TRAFFIC CONTROL DEVICES AS NECESSARY AND IN ACCORDANCE WITH THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES.
- THE CONTRACTOR SHALL BE REQUIRED TO PROVIDE A TELEPHONE NUMBER WHERE THE CONTRACTOR CAN BE REACHED 24 HOURS A DAY, 7 DAYS A WEEK.
- THE LOCATION AND LIMITS OF ALL ON-SITE WORK AND STORAGE AREAS SHALL BE REVIEWED/COORDINATED WITH, AND ACCEPTABLE TO THE TOWN. THE CONTRACTOR SHALL LIMIT ACTIVITIES TO THESE AREAS.
- THE CONTRACTOR SHALL BE REQUIRED TO TEMPORARILY PAVE ALL DISTURBED TRAVEL WAYS, SIDEWALKS & DRIVEWAYS NOT UNDER CONSTRUCTION OR IF LEFT DURING NON WORKING HOURS AND AS REQUIRED BY THE TOWN.


STORMWATER FACILITY OPERATION & MAINTENANCE:

THE CONTRACTOR IS RESPONSIBLE FOR THE PROPER INSPECTION AND MAINTENANCE OF ALL STORMWATER MANAGEMENT FACILITIES AS OUTLINED BELOW UNTIL SUCH TIME THAT THE ROADWAYS AND ASSOCIATED UTILITIES ARE ACCEPTED BY THE OWNER AND THE ENGINEER.

- INSPECT AND RESTORE/CLEAN ALL FACILITIES (INLETS, MANHOLES, INFILTRATION BASINS, ETC.) OF SEDIMENT AND DEBRIS PRIOR TO THE OWNER'S ACCEPTANCE.
- REMOVE AND DISPOSE ALL SEDIMENT AND DEBRIS AT A PRE-APPROVED LOCATION AS APPROVED BY THE TOWN.
- REFER TO THE STORMWATER POLLUTION PREVENTION PLAN (SWPPP) FOR ADDITIONAL INFORMATION PERTAINING TO STORMWATER FACILITY OPERATION AND MAINTENANCE REQUIREMENTS. MAINTAIN A WORKING COPY OF THE SWPPP ON SITE AT ALL TIMES.
- INSPECT AFTER EVERY MAJOR RAINFALL EVENT FOR THE ENTIRE DURATION OF THE CONSTRUCTION PROJECT AND THE FIRST 3 MONTHS AFTER CONSTRUCTION TO ENSURE PROPER STABILIZATION AND CONSTRUCTION.
- MAINTENANCE REQUIRED FOR DRAINAGE STRUCTURES (INLETS, MANHOLES & CATCHBASINS): ALL DRAINAGE STRUCTURES WILL BE INSPECTED BY THE CONTRACTOR TO MONITOR FOR PROPER OPERATION, COLLECTION OF LITTER OR TRASH, AND STRUCTURAL DETERIORATION. THE BASINS WILL BE CLEANED OF SEDIMENT (INCLUDING SUMPS) AS NECESSARY, AND REPAIRED WHEN REQUIRED.

EROSION & SEDIMENT CONTROL (ESC) NOTES:

- REFER TO THE STORMWATER AND POLLUTION PREVENTION PLAN (SWPPP) REGARDING ALL EROSION CONTROL MATTERS. MAINTAIN A WORKING COPY OF THE SWPPP ONSITE AT ALL TIMES. FOLLOW THE SWPPP PROTOCOL FOR SITE MAINTENANCE, INSPECTIONS AND PROPER DOCUMENTATION UNTIL THE SITE HAS BEEN ACCEPTED BY THE OWNER. AT THE COMPLETION OF THE PROJECT THE CONTRACTOR OR OWNER MUST FILE A NOTICE OF TERMINATION WITH NPDES. IN ACCORDANCE WITH NPDES REGULATIONS, THE COMPLETED SWPPP MUST INCLUDE ALL OF THE SITE EROSION CONTROL DOCUMENTATION, WEEKLY EROSION INSPECTION REPORTS COMPLETED BY THE DESIGNATED SITE PERSONNEL, AND ANY OTHER PERTINENT SITE DOCUMENTATION MUST BE RETAINED FOR A MINIMUM OF 3 YEARS FROM THE DATE OF TERMINATION.
- THE CONTRACTOR SHALL DESIGNATE ON-SITE PERSONNEL RESPONSIBLE FOR THE DAILY INSPECTION AND MAINTENANCE OF ALL SEDIMENT AND EROSION CONTROLS AND IMPLEMENTATION OF ALL NECESSARY MEASURES TO CONTROL EROSION AND PREVENT SEDIMENT FROM LEAVING THE SITE.
- INSTALL ALL EROSION AND SEDIMENT CONTROL (ESC) MEASURES AS INDICATED ON DRAWINGS IN CONSULTATION WITH THE ENGINEER BEFORE ANY CONSTRUCTION ACTIVITIES BEGIN. INSPECT, MAINTAIN, REPAIR AND REPLACE EROSION CONTROL MEASURES, AS NECESSARY, DURING THE ENTIRE CONSTRUCTION PERIOD OF THE PROJECT. THE SITE PERIMETER EROSION CONTROLS ARE THE DESIGNATED LIMIT OF WORK. INFORM ALL PERSONNEL WORKING ON THE PROJECT SITE THAT NO CONSTRUCTION ACTIVITY IS TO OCCUR BEYOND THE LIMIT OF WORK AT ANY TIME THROUGHOUT THE CONSTRUCTION PERIOD.
- KEEP THE LIMIT OF CLEARING, GRADING AND DISTURBANCES TO A MINIMUM WITHIN THE PROPOSED AREA OF CONSTRUCTION. PHASE THE SITE WORK IN A MANNER TO MINIMIZE AREAS OF EXPOSED SOIL. IF TREES ARE TO BE CUT, CLEAR AND GRUB ONLY THOSE AREAS WHICH ARE ACTIVELY UNDER CONSTRUCTION. PROPERLY INSTALL THE SEDIMENTATION CONTROLS PRIOR TO BEGINNING ANY LAND CLEARING ACTIVITY AND/OR OTHER CONSTRUCTION RELATED WORK.
- MONITOR LOCAL WEATHER REPORTS DURING CONSTRUCTION AND PRIOR TO SCHEDULING EARTHMOVING OR OTHER CONSTRUCTION ACTIVITIES WHICH LEAVE LARGE DISTURBED AREAS UNSTABILIZED. IF INCLEMENT WEATHER IS PREDICTED, USE BEST PROFESSIONAL JUDGEMENT AND GOOD CONSTRUCTION PRACTICES WHEN SCHEDULING CONSTRUCTION ACTIVITIES AND ENSURE THE NECESSARY EROSION CONTROL DEVICES ARE INSTALLED AND FUNCTIONING PROPERLY TO MINIMIZE EROSION FROM ANY IMPENDING WEATHER EVENTS.
- INSPECT EROSION AND SEDIMENT CONTROL DEVICES AND STABILIZED SLOPES ON A WEEKLY BASIS AND AFTER EACH RAINFALL EVENT OF .25 INCH OR GREATER. REPAIR IDENTIFIED PROBLEMS WITHIN 24 HOURS TO ENSURE EROSION AND SEDIMENT CONTROLS ARE IN GOOD WORKING ORDER. RESET OR REPLACE MATERIALS AS REQUIRED.
- SURROUND THE PERIMETER OF SOIL STOCKPILES WITH SILT SOCK, SILT FENCE, STRAWBALES, OR A COMBINATION OF SILT FENCE WITH STRAWBALE, AS DETERMINED NECESSARY.
- DISTURBED AREAS AND SLOPES MUST NOT BE LEFT UNATTENDED OR EXPOSED FOR EXCESSIVE PERIODS OF TIME SUCH AS THE INACTIVE WINTER SEASON. PROVIDE APPROPRIATE STABILIZATION PRACTICES ON ALL DISTURBED AREAS AS SOON AS POSSIBLE BUT NOT MORE THAN 14 DAYS AFTER THE CONSTRUCTION ACTIVITY IN THAT AREA HAS TEMPORARILY OR PERMANENTLY CEASED. REINFORCE TEMPORARY AREAS HAVING A SLOPE GREATER THAN 4:1 WITH EROSION BLANKETS OR APPROVED EQUAL UNTIL THE SITE IS PROPERLY STABILIZED. TEMPORARY SWALES MAY ALSO BE REQUIRED IF DETERMINED NECESSARY IN THE FIELD BY THE ENGINEER.
- INSTALL A CATCH BASIN SILT SACK OR APPROVED EQUIVALENT IN EACH EXISTING CATCH BASIN RECEIVING RUNOFF FROM THE SITE. UPON THE INSTALLATION OF EACH CATCH BASIN, INSTALL SILT SACK OR APPROVED EQUIVALENT. INSPECT SILT SACKS, AFTER EACH SIGNIFICANT STORM EVENT AND REMOVE AND EMPTY AS NEEDED FOR THE DURATION OF THE CONSTRUCTION PERIOD.
- SMALL SEDIMENTATION BASINS MAY BE CONSTRUCTED ON AN AS-NEEDED BASIS DURING CONSTRUCTION TO AID IN THE CAPTURE OF SITE RUNOFF AND SEDIMENT. IT WILL BE THE RESPONSIBILITY OF THE SITE CONTRACTOR, IN CONSULTATION WITH THE ENGINEER, TO SIZE AND CREATE THESE BASINS IN APPROPRIATE LOCATIONS.
- CONTAIN ALL SEDIMENT ON SITE. SWEEP ALL EXITS FROM THE SITE AS NECESSARY INCLUDING ANY SEDIMENT TRACKING. SWEEP PAVED AREAS AS NEEDED TO REMOVE SEDIMENT AND POTENTIAL POLLUTANTS ACCUMULATED DURING SITE CONSTRUCTION.
- REMOVE ACCUMULATED SEDIMENT FROM ALL TEMPORARY PRACTICES AND DISPOSE OF IN A PRE-APPROVED LOCATION.
- TO ENSURE ALL EROSION AND SEDIMENTATION CONTROL DEVICES ARE PROPERLY MAINTAINED AND REPAIRED IN A TIMELY AND RESPONSIBLE MANNER, PROVIDE ON SITE,OR MAKE READILY AVAILABLE, THE NECESSARY EQUIPMENT AND SITE PERSONNEL DURING CONSTRUCTION HOURS FOR THE DURATION OF THE PROJECT. IF SITE WORK IS SUSPENDED DURING THE WINTER MONTHS THE CONTRACTOR MUST CONTINUE TO PROVIDE PERSONNEL AND EQUIPMENT ON SITE OR READILY AVAILABLE .
- CONTROL DUST BY WATERING OR OTHER APPROVED METHODS AS NECESSARY, OR AS DIRECTED BY THE ENGINEER.



				Scale	AS NOTED
				Date	MARCH 2021
				Job No.	R309-2009
				Designed by	AMF
				Drawn by	AMF
				Checked by	MES
				Approved by	JDF
MARK	DATE	DESCRIPTION			

THIS LINE IS ONE INCH LONG WHEN PLOTTED AT FULL SCALE ON A 22" X 34" DRAWING

MISCELLANEOUS PAVING - PAVEMENT MANAGEMENT PROGRAM - 2021
WESTWOOD, MA

GENERAL NOTES

Sheet No.

03



DOVER

WESTWOOD

NORWOOD

PROPOSED HMA SPEED HUMP (160'± NORTH OF WESTCHESTER DRIVE)

PROPOSED HMA SPEED HUMP (265'± SOUTH OF WESTCHESTER DRIVE)

PROPOSED HMA SPEED HUMP (415'± NORTH OF HARTFORD STREET)

END PAVING BEFORE TEXTURIZED DECORATIVE CROSSWALKS AT HIGH STREET (ROUTE 109) INTERSECTION

PAVING ENDS 260'± WEST OF WINTER STREET

PAVING ENDS 145'± WEST OF OAK STREET

PAVING STARTS 75'± EAST OF ARCADIA ROAD

Legend

- Proposed paving and centerline/shoulder striping (TYP)
- Proposed paving and centerline/shoulder striping. See sheet 07 for further information.


MARCH 2021



Paving List			
Street Name	From Street	To Street	Length (FT)
HIGH ROCK STREET	DOVER ROAD	HIGH STREET (ROUTE 109)	2,800
HARTFORD STREET	WESSEX DRIVE	HIGH STREET (ROUTE 109)	3,300
POND STREET	HIGH STREET (ROUTE 109)	145'± WEST OF OAK STREET	1,800
POND STREET	75'± EAST OF ARCADIA ROAD	MARTINGALE LANE	1,700
CLAPBOARDTREE STREET	POND STREET	260'± WEST OF WINTER STREET	700


MISCELLANEOUS PAVING - PAVEMENT MANAGEMENT PROGRAM - 2021
 WESTWOOD, MA
 LOCUS MAP






**HIGH ROCK STREET
DOVER ROAD TO WESTCHESTER DRIVE**

N.T.S.




**HIGH ROCK STREET
WESTCHESTER DRIVE TO HIGH STREET (ROUTE 109)**

N.T.S.




**HARTFORD STREET
WESSEX DRIVE TO HIGH STREET (ROUTE 109)*****

N.T.S.




**POND STREET
HIGH STREET (ROUTE 109) TO CLAPBOARDTREE STREET******

N.T.S.



**POND STREET
CLAPBOARDTREE STREET TO MARTINGALE LANE**

N.T.S.



**CLAPBOARDTREE STREET
POND STREET TO 260' WEST OF WINTER STREET**

N.T.S.

PAVEMENT NOTES

PROPOSED PAVEMENT MILLING & OVERLAY

SURFACE: 2" SUPERPAVE SURFACE COURSE 12.5 (SSC-12.5)
OVER
ASPHALT EMULSION FOR TACK COAT (RS-H) @ 0.08
GAL/SY OVER

*LEVELING: VARIABLE DEPTH AS DIRECTED BY THE TOWN IF
NEEDED TO ADJUST CROSS SLOPE

MILLING: 2" PAVEMENT MILLING

PROPOSED HOT MIX ASPHALT DRIVEWAY

SURFACE: 1.5" SUPERPAVE SURFACE COURSE 12.5 (SSC-12.5)
OVER


2.5" SUPERPAVE INTERMEDIATE COURSE 12.5
(SIC-12.5) OVER

SUBBASE: 8" GRAVEL BORROW, TYPE B

TYPICAL SECTION NOTES

- ALL HOT MIX ASPHALT PAVEMENT SHALL BE PER SECTION 450
HOT MIX ASPHALT AND SECTION M3 ASPHALTIC MATERIALS.
- CONTRACTOR SHALL MAKE ADJUSTMENTS TO GRADING TO
PROVIDE ADEQUATE DRAINAGE AT THE DIRECTION OF THE
TOWN OR ENGINEER.

- * LEVELING COURSE TO BE PAID FOR UNDER ITEM 450.53.
SUPERPAVE LEVELING COURSE - 12.5 (SLC - 12.5) AT THE
DIRECTION OF THE TOWN.
- ** EXISTING SIDEWALK TO BE RECONSTRUCTED UNDER A
SEPARATE CONTRACT, THE CONTRACTOR SHALL COORDINATE
WITH THE SIDEWALK CONTRACTOR TO SCHEDULE ROADWAY
PAVING TO THAT ENSURE ALL SIDEWALK WORK IS COMPLETED
BEFORE THE PAVING WORK STARTS.
- **** PAVING TO END TO THE WEST OF THE TEXTURIZED
DECORATIVE CROSSWALKS AT THE HIGH STREET (ROUTE 109)
INTERSECTION.
- **** PAVING FROM 145'± WEST OF OAK STREET TO 75'± EAST OF
ARCADIA ROAD TO BE COMPLETED BY OTHERS.



Scale	NOT TO SCALE	
Date	MARCH 2021	
Job No.	R309-2009	
Designed by	AMF	
Drawn by	AMF	
Checked by	MES	
Approved by	JDF	
MARK	DATE	DESCRIPTION

THIS LINE IS ONE
INCH LONG WHEN
PLOTTED AT FULL
SCALE ON A 22" X
34" DRAWING




MISCELLANEOUS PAVING - PAVEMENT MANAGEMENT PROGRAM - 2021
WESTWOOD, MA

TYPICAL SECTIONS

Sheet No.

05

Drawing file: I:\Westwood\309-2009\Road Bond Support Services\MISCELLANEOUS PAVING - PAVEMENT MANAGEMENT PROGRAM - 2021\CAD\05 TYPICALS.dwg Plot Date: Mar 02 2021 3:18pm




NOTE:

1. ALL 12" LINES SHALL BE APPLIED IN ONE APPLICATION, NO COMBINATION OF LINES (e.g. TWO - 6" LINES) WILL BE ACCEPTED.


CHANNELIZED MARKINGS - MEDIAN FOR ROADWAYS 40MPH OR LESS

N.T.S.



STAMPED ASPHALT MEDIAN

N.T.S.





NOTES:

1. YIELD LINES SHALL CONSIST OF A ROW OF SOLID WHITE TRIANGLES.
2. IF APPLICABLE, YIELD LINES SHALL BE PLACED 4- FEET IN ADVANCE OF THE NEAREST CROSSWALK LINE.
3. IN THE ABSENCE OF A MARKED CROSSWALK, YIELD LINES SHALL BE PLACED AS SHOWN ON THE PLANS.

YIELD LINE TRIANGLES

N.T.S.




DISTANCE (FEET)	0.0	1.0	2.0	3.0	4.0	5.0	6.0	7.0
FINISHED HEIGHT (INCHES)	0.0	0.8	1.5	2.0	2.4	2.8	2.9	3

SECTION A-A: GEOMETRY DETAIL

HOT MIX ASPHALT SPEED HUMP

N.T.S.



ZEBRA STYLE CROSSWALK - 12" WIDE LINES

N.T.S.

NOTES:

1. ALL 12" LINES SHALL BE APPLIED IN ONE APPLICATION, NO COMBINATION OF LINES (TWO - 6" LINES) WILL BE ACCEPTED.
2. LAYOUT OF CROSSWALKS SHALL BE APPROVED BY THE TOWN AND/OR ENGINEER PRIOR TO APPLICATION.
3. ALL CROSSWALKS INSTALLED SHALL CONFORM TO THE RELEVANT PROVISIONS OF THE COMMONWEALTH OF MASSACHUSETTS DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR HIGHWAYS AND BRIDGES DATED 2021, SECTION 860 FOR REFLECTORIZED LINE & MATERIAL M7.01.03.



MARK	DATE	DESCRIPTION

Scale	AS NOTED
Date	MARCH 2021
Job No.	R309-2009
Designed by	AMF
Drawn by	AMF
Checked by	MES
Approved by	JDF


THIS LINE IS ONE INCH LONG WHEN PLOTTED AT FULL SCALE ON A 22" X 34" DRAWING

MISCELLANEOUS PAVING - PAVEMENT MANAGEMENT PROGRAM - 2021
WESTWOOD, MA

CONSTRUCTION DETAILS

Sheet No.

06





CONSTRUCTION NOTES:

1. ALL PROPOSED WORK SHOWN ON THE EXISTING AERIAL PLANS ARE APPROXIMATE IN NATURE. THE INTENT OF THIS GRAPHIC IS FOR BIDDING PURPOSES ONLY. ALL LIMITS OF WORK SHALL BE FIELD VERIFIED WITH THE TOWN PRIOR TO THE COMMENCEMENT OF ANY WORK.
2. THE SIDEWALKS, WHEELCHAIR RAMPS, AND RAISED MEDIAN ISLAND ARE TO BE BUILT BY OTHERS. COORDINATION IS REQUIRED TO ENSURE THAT PROPOSED ROADWAY CONSTRUCTION TAKES PLACE AFTER CONSTRUCTION BY OTHERS.
3. THE CONSTRUCTION WITHIN THIS PROJECT SHALL BE HANDLED AS A BOOKJOB. FINAL LAYOUT AND GRADING OF THE ROADWAY AND DRIVEWAYS SHALL BE DETERMINED BY THE CONTRACTOR IN THE FIELD IN COORDINATION WITH THE TOWN AND SHALL BE COMPLIANT WITH THE APPLICABLE STATE OR FEDERAL STANDARDS.
4. PAVEMENT MILL AND OVERLAY OPERATIONS SHALL RETAIN SIMILAR GRADING AS EXISTING. THE CONTRACTOR SHALL ENSURE THAT ADEQUATE CROSS SLOPES ARE MAINTAINED AND SHALL ENSURE THAT EXISTING DRAINAGE PATTERNS ARE MAINTAINED AND IN COORDINATION WITH THE TOWN.

PAVEMENT MARKING NOTES:

1. PROPOSED PAVEMENT MARKINGS SHALL ALIGN WITH SIGNS INSTALLED BY OTHERS AND AS DIRECTED BY THE TOWN.
2. ALL PAVEMENT MARKINGS WITHIN THE LIMITS OF WORK SHALL BE EPOXY UNLESS OTHERWISE NOTED.
3. WHERE EXISTING PAVEMENT MARKINGS ARE DIFFERENT THAN PROPOSED MARKINGS SHOWN, REMOVE BY AN APPROVED METHOD.



MARK	DATE	DESCRIPTION

Scale	AS NOTED
Date	MARCH 2021
Job No.	R309-2009
Designed by	AMF
Drawn by	AMF
Checked by	MES
Approved by	JDF

THIS LINE IS ONE INCH LONG WHEN PLOTTED AT FULL SCALE ON A 22" X 34" DRAWING

MISCELLANEOUS PAVING - PAVEMENT MANAGEMENT PROGRAM - 2021
WESTWOOD, MA

CONSTRUCTION PLANS & PAVEMENT MARKING PLANS
POND STREET & CLAPBOARDTREE STREET

Sheet No.
07

Drawing file: I:\Westwood\309-2009-Road Bond Support Services\MISCELLANEOUS PAVING - PAVEMENT MANAGEMENT PROGRAM - 2021\CAD\07_POND-CLAPBOARD PMS.dwg Plot Date: Mar 01, 2021 16:23pm